

United States Department of the Interior  
National Park Service

F-6-21B

National Register of Historic Places  
Registration Form

This form is for use in nominating or requesting determinations of eligibility for individual properties or districts. See instructions in *Guidelines for Completing National Register Forms* (National Register Bulletin 16). Complete each item by marking "x" in the appropriate box or by entering the requested information. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, styles, materials, and areas of significance, enter only the categories and subcategories listed in the instructions. For additional space use continuation sheets (Form 10-900a). Type all entries.

## 1. Name of Property

historic name Maryland Tuberculosis Sanatorium Administration Building  
other names/site number Cullen, Victor, Center Old Administration Building (preferred) ~~F-16-21B~~

## 2. Location

street & number Victor Cullen Center Campus N/A not for publication  
city, town Sabillasville N/A vicinity  
state Maryland code MD county Frederick code 021 zip code 21780

## 3. Classification

## Ownership of Property

- ☐ private  
☐ public-local  
☒ public-State  
☐ public-Federal

## Category of Property

- ☒ building(s)  
☐ district  
☐ site  
☐ structure  
☐ object

## Number of Resources within Property

Contributing	Noncontributing
1	buildings
0	sites
0	structures
0	objects
1	0 Total

Name of related multiple property listing:

N/A

Number of contributing resources previously  
listed in the National Register 0

## 4. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act of 1966, as amended, I hereby certify that this  
☒ nomination ☐ request for determination of eligibility meets the documentation standards for registering properties in the  
National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60.  
In my opinion, the property ☒ meets ☐ does not meet the National Register criteria. ☐ See continuation sheet.

Signature of certifying official

STATE HISTORIC PRESERVATION OFFICER

State or Federal agency and bureau

Date

7/9/90

In my opinion, the property ☐ meets ☐ does not meet the National Register criteria. ☐ See continuation sheet.

Signature of commenting or other official

Date

State or Federal agency and bureau

## 5. National Park Service Certification

I, hereby, certify that this property is:

- ☒ entered in the National Register.  
☐ See continuation sheet.  
☐ determined eligible for the National  
Register. ☐ See continuation sheet.  
☐ determined not eligible for the  
National Register.  
☐ removed from the National Register.  
☐ other, (explain:)

8/22/90

Signature of the Keeper

Date of Action

United States Department of the Interior  
National Park Service

**National Register of Historic Places  
Continuation Sheet**

Victor Cullen Center Old Administration Building  
Frederick County, Maryland F-6-21B

Section number \_\_\_\_\_ Page \_\_\_\_\_

**SUPPLEMENTARY LISTING RECORD**

NRIS Reference Number: 90001228

Date Listed: 8/22/90

Victor...Administration Building  
Property Name

Frederick  
County

MD  
State

Multiple Name

-----  
This property is listed in the National Register of Historic Places in accordance with the attached nomination documentation subject to the following exceptions, exclusions, or amendments, notwithstanding the National Park Service certification included in the nomination documentation.

*Patrick Andrews*

*for* Signature of the Keeper

*8/22/90*

Date of Action

=====

**Amended Items in Nomination:**

The current function of the building had to be clarified. The nomination form lists its function as Health Care, but from the photos it appears to be vacant. Ron Andrews with the MD SHPO says that the building is vacant. The form is now officially amended to include this information.

**DISTRIBUTION:**

National Register property file  
Nominating Authority (without nomination attachment)

**6. Function or Use**~~F-1-6-21B~~

Historic Functions (enter categories from instructions)

HEALTH CARE/sanitarium

Current Functions (enter categories from instructions)

HEALTH CARE/sanitarium

**7. Description**

Architectural Classification

(enter categories from instructions)

Colonial Revival

Materials (enter categories from instructions)

foundation stone

walls stone

wood

roof slate

other wood

Describe present and historic physical appearance.

DESCRIPTION SUMMARY:

The Old Administration Building is a seven bay, 2-1/2 story stone and frame structure located on a hillside and facing south. It has four stone chimneys, two on each gable end, a slate roof with dormers and a modillion block cornice. A parapet with a lunette window connects the chimneys. The principal entrance has a circular fanlight under an elliptical frame and complex, leaded sidelights. A pedimented porch with an elliptical ceiling covers the entrance. It has a dentilated cornice and an elliptical arch with a keystone between two pairs of Roman Doric columns. On the second floor over the porch is a three-part, flat-headed window. To the rear, but connected to the administration building, is the original dining hall and kitchen. The first floor is stone and the second frame with a hipped roof. Eight detached frame patient pavillions once flanked these buildings. These T-shaped buildings (now demolished) each accommodated twenty patients arranged in two wards or porches, 14 x 50 feet facing south. In the rear, the stem of the T, were dressing rooms, toilet and bath facilities. They were not heated and every part of every room had cross ventilation and light on opposite sides. Between the porch columns were large sliding sashes arranged for maximum air even during inclement weather when the beds needed protection.

# 8. Statement of Significance

F-6-21B  
F-1-6-21B

Certifying official has considered the significance of this property in relation to other properties:

☐ nationally ☒ statewide ☐ locally

Applicable National Register Criteria ☒ A ☐ B ☐ C ☐ D

Criteria Considerations (Exceptions) ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Areas of Significance (enter categories from instructions)

Health/Medicine

Period of Significance

1907

Significant Dates

1907

Cultural Affiliation

N/A

Significant Person

N/A

Architect/Builder

Wyatt and Nolting, architects

State significance of property, and justify criteria, criteria considerations, and areas and periods of significance noted above.

## SIGNIFICANCE SUMMARY:

The significance of the Old Administration Building at the Victor Cullen Center is derived from association with the Maryland Tuberculosis Sanatorium, the first state supported institution of its type in Maryland. In response to a marked increase in the number of cases of tuberculosis in the state and the absence of private medical facilities for treatment, the Maryland General Assembly approved funds for the construction and maintenance of a sanatorium on April 5, 1906. An appropriation of \$50,000 for each year, 1907 and 1908, for land purchase and building construction and a \$15,000 annual support beginning in 1907 was to be paid to a Board of Managers for the new sanatorium. Based on designs drawn by the Baltimore architectural firm of Wyatt and Nolting, development of the complex began in 1907. The first structure was the administration building followed by the power house in 1908 and various other buildings in succeeding years. Today only the administration building and the power house remain from the period when the institution functioned as the tuberculosis sanatorium before conversion to the Victor Cullen School. Unfortunately these buildings are separated by expanses of non-contributing new structures. Although the setting of the institution and a significant number of the historic elements have been destroyed over time, the Maryland Tuberculosis Sanatorium is an important milestone historically in the state's efforts to maintain the general welfare of its population. Four similar institutions were built by the state but not until the 1920s using the Frederick County institution as the basis for designing the state's continued involvement in the health of the citizens.

☒ See continuation sheet No. 8.1

for HISTORIC CONTEXT and MARYLAND COMPREHENSIVE  
HISTORIC PRESERVATION PLAN data.

## Previous documentation on file (NPS):

- ☐ preliminary determination of individual listing (36 CFR 67) has been requested
- ☐ previously listed in the National Register
- ☐ previously determined eligible by the National Register
- ☐ designated a National Historic Landmark
- ☐ recorded by Historic American Buildings Survey # \_\_\_\_\_
- ☐ recorded by Historic American Engineering Record # \_\_\_\_\_

☒ See continuation sheet No. 9.1

## Primary location of additional data:

- ☒ State historic preservation office
- ☐ Other State agency
- ☐ Federal agency
- ☐ Local government
- ☐ University
- ☐ Other

Specify repository: \_\_\_\_\_

## 10. Geographical Data

Acreage of property less than one acreUSGS quad Blue Ridge Summit, PA-MD

## UTM References

A	1 8	2 8 9 3 5 0	4 3 9 8 3 8 0
	Zone	Easting	Northing
C			

B			
	Zone	Easting	Northing
D			

☐ See continuation sheet

## Verbal Boundary Description

☒ See continuation sheet No. 10.1

## Boundary Justification

The boundaries include the minimum amount of land to provide a setting but exclude recent surrounding changes to the campus.

☐ See continuation sheet

## 11. Form Prepared By

name/title	<u>George Andreve, Project Review &amp; Compliance Administrator</u>		
organization	<u>Maryland Historical Trust</u>	date	<u>March 1989</u>
street & number	<u>21 State Circle</u>	telephone	<u>301-974-5007</u>
city or town	<u>Annapolis</u>	state	<u>Maryland</u> zip code <u>21401</u>



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetCullen, Victor, Center  
Old Administration Building  
Frederick County, Maryland

F-6-21B

Section number 7 Page 7.1

## GENERAL DESCRIPTION

The Old Administration Building is a seven bay, 2-1/2 story stone and frame structure located on a hillside and facing south. It has four stone chimneys, two on each gable end, a slate roof with dormers and a modillion block cornice. A parapet with a lunette window connects the chimneys. The principal entrance has a circular fanlight under an elliptical frame and complex, leaded sidelights. A pedimented porch with an elliptical ceiling covers the entrance. It has a dentilated cornice and an elliptical arch with a keystone between two pairs of Roman Doric columns. On the second floor over the porch is a three-part, flat-headed window. To the rear, but connected to the administration building, is the original dining hall and kitchen. The first floor is stone and the second frame with a hipped roof. Eight detached frame patient pavillions once flanked these buildings. These T-shaped buildings (now demolished) each accommodated twenty patients arranged in two wards or porches, 14 x 50 feet facing south. In the rear, the stem of the T, were dressing rooms, toilet and bath facilities. They were not heated and every part of every room had cross ventilation and light on opposite sides. Between the porch columns were large sliding sashes arranged for maximum air even during inclement weather when the beds needed protection.

The administration building appears to be two separate buildings, one in front of the other, originally connected only on the first floor and basement. In the front part were the administrative offices, reception rooms, physicians offices, examining rooms and the offices of the superintendent and nurses. On the second and third floor were bedrooms for the staff. There is a large, centrally located staircase to the rear of and screened from the central corridor. In the basement were storage rooms. The main floor of the rear building housed a large dining room for patients. It has been divided into smaller rooms. In the basement was the kitchen, bakery, storerooms and refrigerating plant, and the refrigerator and bake oven remain. An infirmary with twenty beds and a diet kitchen was initially located in the second floor frame part which was regarded as temporary by the Board of Managers when it was built. Most beds were in small private rooms with covered porches. The first-floor lobby connecting the two buildings served as the entrance for patients going

United States Department of the Interior  
National Park Service

**National Register of Historic Places  
Continuation Sheet**

Cullen, Victor, Center  
Old Administration Building  
Frederick County, Maryland

F-6-21B

Section number 7 Page 7.2

---

to the dining room and an amusement hall. Because the basement kitchen proved to be intolerably hot, hard to ventilate, keep clean and free of flies and was inaccessible from the dining room, a new, above ground kitchen with nurses quarters on the second floor was built to the rear of the dining hall in 1913. Two terraces to the rear of the old dining room were enclosed for dining rooms for the staff and nurses. A new infirmary was built in 1910, and the nurses were housed in its original quarters. The nursing school, which graduated its first class in 1912, also expanded the nurses' requirements, and a second floor "rest room" for them was added to the bridge between the two stone buildings.

United States Department of the Interior  
National Park Service

**National Register of Historic Places**  
**Continuation Sheet**

F-6-21B  
~~F-1-6-21B~~

Cullen, Victor, Center  
Old Administration Building  
Frederick County, Maryland

Section number 8 Page 8.1

---

HISTORIC CONTEXT:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont

Chronological/Developmental Period(s):

Industrial Urban Dominance A.D. 1870-1930

Prehistoric/Historic Period Theme(s):

Social/Educational/Cultural/Architecture/Landscape Architecture/  
Community Planning

Resource Type:

Category: building

Historic Environment: rural

Historic Function(s) and Use(s): HEALTH CARE/sanitarium

Known Design Source: Wyatt and Nolting



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation Sheet

F-6-21B

~~F-1-6-21B~~Cullen, Victor, Center  
Old Administration Building  
Frederick County, MarylandSection number 8 Page 8.2HISTORIC CONTEXT:

The Victor Cullen Center, located north of Sabillasville and east of Maryland Route 81, was built as the Maryland Tuberculosis Sanatorium. The first official recognition of the tuberculosis problem in Maryland was in a letter of November 5, 1901, from the Secretary of the State Board of Health to Governor John Walter Smith. He pointed out work in other states, asked for an investigation of the conditions in Maryland and recommended the appointment of a tuberculosis commission to do this. After his interview with Governor Smith the following month urging the need for state sanatoria, a bill establishing the commission was submitted and passed in 1902. On January 15, 1904, the commission sponsored a Tuberculosis Exposition in McCoy Hall at the Johns Hopkins University to educate citizens and give instruction to those afflicted. There were lectures and exhibits from throughout the United States and Europe. The largest exhibits, but secondary in importance to state and municipal prophylaxis, were those on hospitals and sanatoria which promoted the rest, food and fresh air treatment. According to Dr. S. A. Knoph of New York City, "Tuberculosis Expo...mark(ed) an epoch in the history of the anti-tuberculosis crusade in America." He advocated that philanthropists give playgrounds and parks for children and sanatoria for the consumptive poor rather than more libraries and colleges; for, as he noted, "experiments show that animals deprived of light and good air succumb to an inoculation of tuberculosis more rapidly than others which can roam about in sunshine and fresh air.

Tuberculosis Expo, then, was the influential event and a major force which ultimately pushed the state into action. At Expo's opening, Governor Edwin Warfield recognized the proper treatment confronted the state as a social problem and noted he had no idea that TB existed to such an extent in Maryland which had over 10,000 cases and 2,500 deaths in 1903. In the interest of the people, he noted there was no appropriation for suppression and reduction of TB and advocated that proper sanatoria for treatment of early cases and care of advanced cases be established instead of forcing advanced cases to poorhouses and city hospitals. The General Assembly then approved funds for erection and maintenance of a sanatorium on April 1, 1906. An appropriation of \$50,000 for each year, 1907 and 1908, for land purchase and erection of buildings and \$15,000 annual support beginning in 1907 was to be paid to a Board of Managers for the new sanatorium.

The Board of Managers of the Maryland Tuberculosis Sanatorium replaced the Governor's TB Commission. At their organizational meeting on September 20, 1906, they appointed subcommittees to study geographical and climatological conditions of the state to secure a suitable site and to formulate plans for construction as well as to

United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation Sheet

F-6-21B

F-1-6-21B

Cullen, Victor, Center  
Old Administration Building  
Frederick County, MarylandSection number 8 Page 8.3HISTORIC CONTEXT:

outline the scope for which the institution should be intended. The TB Commission had made recommendations regarding the type of location, and the Site Committee adopted theirs:

1. Minimum altitude of 1,000 feet (sabillasville site is 1,450 feet);
2. Situated on a southerly or southeasterly slope (site is on the southern slope of Loop Mountain overlooking Sabillasville and Hanover and Gettysburg Valley);
3. Protected by woodlands or hills on the north (mountains and Gettysburg Gap are to the north);
4. Soil should be dry, porous and capable of good drainage;
5. Atmosphere as free of moisture as possible;
6. Minimum tract of 100 acres (site has 198 acres);
7. Unlimited water supply by using the local public water system or one of its own (site provided three springs producing 100 gallons/minute and a 150 foot artesian well);
8. Near a railroad for patients, friends and economical hauling of supplies and a separate station if possible (site on the main line of the Western Maryland Railroad which erected Sanatorium Station and built a line to the nearby power plant).
9. No further from chief population centers than the above conditions necessitate (site is 69 miles from Baltimore and was served by two daily trains each way).

The Commission contacted the Baltimore architectural firm of Wyatt and Nolting. The original plan recommended an administration building, a dining hall for 100-150 at the rear of the main building, but connected with it by a short gallery and a kitchen with sleeping rooms for domestics on the upper floor. The patients' pavilions were to face south and formed east and west wings to the main building. The scheme was Colonial Revival, but what was finally built from local rubble was a simplification of the original design and somewhat less elegant.

United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetCullen, Victor, Center  
Old Administration Building  
Frederick County, Maryland

F-1-6-21B

Section number 8 Page 8.4HISTORIC CONTEXT:

The Sanatorium was built to alleviate a growing medical problem. At full development, it was to serve 250 Maryland patients whose only choice before was to go to Eudowood Sanatorium in Towson (less than 40 beds) and its branch in Mt. Airy or a Baltimore city hospital receiving state aid which would admit TB patients. The majority went to insane asylums, prisons, almshouses or private dwellings. It was claimed that 80% of those treated in the four sanatoria located in other states were able to return to work. At moderate charge of \$3.50 per week, consumptives could receive fresh air treatment advocated by Hippocrates in 375 B.C. combined with the modern sanatorium treatment begun by Dr. George Bodington of Warwickshire, England, in 1835. Under medical supervision, they were given a nutritious diet of milk, eggs and fresh meats with an abundance of fresh air, both day and night. In 1909, the Board of Managers reported to the Governor that maintenance costs of \$6.65 per week per patient less patient charges (net cost to the state was \$3.99) made the Maryland Sanatorium the most economically administered institution of its kind in the country. The original buildings which opened in August of 1908 (formally on May 15, 1909) with 210 patients expanded as governmental projects do to meet growing needs until reaching a capacity of 450 in 1913. It then was able to serve hopelessly ill patients as well as those who had prospects of improvement. The sanatorium, now renamed for its first superintendent, Dr. Victor F. Cullen, was the first of four similar Maryland state-supported hospitals -- The Henryton Sanatorium in Carroll County for blacks opened 1923, Mt. Wilson in Baltimore County in 1925, and the Eastern Shore Tuberculosis Sanatorium of Salisbury in 1928.

Construction of the complex was the responsibility of a Board of Managers created by the State Legislature in 1906. After studying every existing sanatorium in the United States and many abroad, their Planning Committee recommended a central administration building and dining hall flanked by detached patient pavilions or shacks. The two principal buildings, generally neo-Georgian, were designed by the Baltimore architectural firm of Wyatt and Nolting. They were built of local rubble in 1907-1908 by Henry Smith, Sons and Company who submitted the lowest bid of \$66,760. Comparative bids showed the cost of stone and frame construction to be about the same due to the high price of lumber. Because of an abundance of superficial stone rubble on the site, the Board of Managers decided to use it since it was more durable, required less repair and cost much less to insure. The seven-bay, 2 1/2-story Administration Building is located on a hillside and faces south.

United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation Sheet

F-6-21B

~~F-1-6-21B~~Section number 8 Page 8.5Cullen, Victor, Center  
Old Administration Building  
Frederick County, MarylandHISTORIC CONTEXT:

The administration building appears as two separate buildings one in front of the other, originally connected only on the first floor and basement. In the front part were the administrative offices, reception rooms, physicians' offices, examining rooms and the offices of the superintendent and nurses. On the second and third floors were bedrooms for the staff. In the basement were storage rooms. The main floor of the rear building housed a large dining room for patients. It has been divided into smaller rooms. In the basement was the kitchen, bakery, storerooms and refrigerating plant, and the refrigerator and bake oven remain. An infirmary with twenty beds and a diet kitchen was initially located in the second floor frame part which was regarded as temporary by the Board of Managers when it was built. Most beds were in small private rooms with covered porches. The first-floor lobby connecting the two buildings served as the entrance for patients going to the dining room and an amusement hall. Because the basement kitchen proved to be intolerably hot, hard to ventilate, keep clean and free of flies and was inaccessible from the dining room, a new, above ground kitchen with nurses quarters on the second floor was built to the rear of the dining hall in 1913. Two terraces to the rear of the old dining room were enclosed for dining rooms for the staff and nurses. A new infirmary was built in 1910, and the nurses were housed in its original quarters. The nursing school, which graduated its first class in 1912, also expanded the nurse's requirements, and a second floor "rest-room" for them was added to the bridge between the two stone buildings.

On the side of the hill facing State Route 81 is the power building built in 1908 at a cost of \$21,000. All the power, light and heat for the sanatorium was generated in the basement of this building which is above grade on the rear (west) side. On the first floor were the laundry, workshop and morgue with two apartments for employees on the second floor. The mechanical plant, most of which still remains, had a boiler capacity of 250 horsepower arranged in duplicate units. There was an electric generating plant of 120 KW in duplicate units with the necessary engines, pumps and other apparatus. Electric was used for general lighting, power in the water pumping plant and the laundry. Exhaust steam was piped to the hospital buildings for heat and generating hot water. Before the power plant was built, the hospital used kerosene lamps. The entrance to the building is on the east and visitors and patients arriving at Sanatorium Station first passed the power house following the road along a ridge which paralleled a railroad siding for the coal cars.



United States Department of the Interior  
National Park Service

National Register of Historic Places  
Continuation Sheet

F-6-21B

~~F-1-6-21B~~

Cullen, Victor, Center  
Old Administration Building  
Frederick County, Maryland

Section number 8 Page 8.6

HISTORIC CONTEXT:

In 1914, a small, two-story laboratory building was built northwest of the administration building adjacent to a general expansion of the facilities. A new 520 foot long reception hospital

which opened in August of 1912 with 200 beds, 100 in private rooms, was built for more advanced cases. At that time the boiler capacity of the power plant was doubled with a new Fitzgibbons boiler. The hospital wing has been demolished, but part of the kitchen and dining facilities remain but in poor condition.

The sanatorium also included a working farm with a barn, cow stable, outbuildings for pigs, chickens and Belgian hares. Most of the buildings have been demolished including the farm buildings, infirmary building, children's pavilion, amusement hall, patients shacks, and laboratory building.

United States Department of the Interior  
National Park Service

**National Register of Historic Places**  
**Continuation Sheet**

F-6-21B

~~F-1-6-21B~~

Cullen, Victor, Center  
Old Administration Building  
Frederick County, Maryland

Section number 9 Page 9.1

MAJOR BIBLIOGRAPHICAL REFERENCES:

Report of the Tuberculosis Commission of the State of Maryland, 1902-1904. Dr. William S. Thayer, President, Baltimore: The Sun Job Printing Office, 1904.

Second Report of the Tuberculosis Commission of Maryland, 1906.

First Annual Report of the Board of Managers of the Maryland Tuberculosis Sanatorium, January 1, 1908. Baltimore: The Sun Job Printing Office, 1908. (Also Second through Twenty-first Reports.)

Laws of Maryland, 1906, 1908.

Maryland Inventory of Historic Properties: Maryland Historical Trust, Annapolis, Maryland.



## MARYLAND HISTORICAL TRUST WORKSHEET

NATIONAL REGISTER  
QUALITY - NEEDS  
IMMEDIATE ATTENTION

## NOMINATION FORM

for the

NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE



**1. NAME**

COMMON: MAIN BUILDING, VICTOR CULLEN INSTITUTE

AND/OR HISTORIC: \_\_\_\_\_

**2. LOCATION**

STREET AND NUMBER: ex. that building of the VICTOR CULLEN INSTITUTE, 1/4 MI. EAST OF MD RT 91, north of SABILLASVILLE

CITY OR TOWN: SABILLASVILLE (CHAMBERS ELECTION DISTRICT)

STATE: \_\_\_\_\_ COUNTY: FREDERICK

**3. CLASSIFICATION**

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object	<input checked="" type="checkbox"/> Public <input type="checkbox"/> Private <input type="checkbox"/> Both	<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input checked="" type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input type="checkbox"/> No

PRESENT USE (Check One or More as Appropriate)

<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input checked="" type="checkbox"/> Other (Specify) INSTITUTION	<input type="checkbox"/> Comments IN ZONE OF DEVELOPMENT
--	--	--	---	--

**4. OWNER OF PROPERTY**

OWNER'S NAME: STATE OF MARYLAND DEPARTMENT OF HEALTH & MENTAL HYGIENE  
MENTAL RETARDATION ADMINISTRATION

STREET AND NUMBER: 301 WEST PRESTON ST

CITY OR TOWN: BALTIMORE STATE: MD ZIP: 21201

**5. LOCATION OF LEGAL DESCRIPTION**

COURTHOUSE, REGISTRY OF DEEDS, ETC:

STREET AND NUMBER:

CITY OR TOWN: STATE:

Title Reference of Current Deed (Book & Pg. #):

**6. REPRESENTATION IN EXISTING SURVEYS**

TITLE OF SURVEY: F-10-57

DATE OF SURVEY: ☐ Federal ☐ State ☐ County ☐ Local

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN: STATE:

## 7. DESCRIPTION

CONDITION

☐ Excellent☒ Good☐ Fair

(Check One)

☐ Deteriorated☐ Ruins☐ Unexposed

(Check One)

☐ Altered☒ Unaltered

(Check One)

☐ Moved☒ Original Site

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

THIS ELEGANT WELL EXECUTED 2½ STORY STONE BUILDING, WITH A LONG AND COMPLEX REAR WING OF STONE AND SHINGLE, WAS THE MAIN BUILDING OF THE VICTOR CULLEN INSTITUTE WHEN IT OPENED IN THE EARLY 20th CENTURY AS A TUBERCULOSIS SANATORIUM

FOR WELL TO DO PEOPLE ON THE EAST COAST. THE MAIN BLOCK IS

A FINE EXAMPLE OF GOOD COLONIAL REVIVAL AND THE WING IS JUST AS GOOD AN EXAMPLE OF THE CONTEMPORARY ARCHITECTURE OF THE TIME. BOTH BLEND TOGETHER EXTREMELY WELL BECAUSE OF THE USE OF THE SAME ROUGH LAID STONE AND DARK GREEN PAINT. ALL AROUND


AN EXCELLANT BUILDING.

THE MAIN BLOCK IS 2½ STORIES HIGH AND HAS A STONE CHIMNELS, A FINE MODILLION BLOCK CORNICE, SLATE ROOF, ELEGANT DORMERS, AND LARGE 1/1 WINDOWS. WITH STONE STEPS.

THE MAIN (SOUTH) FACADE IS 7 BAYS WIDE WITH A VERY FINE DOORWAY IN THE CENTER BAY THAT HAS A CIRCULAR FANLIGHT UNDER THE ELLIPTICAL FRAME AND ELABORATE SIDELIGHTS, ALL WITH LEADED MUNTINS. THERE IS A FINE 4 POST PEDIMENTED PORCH WITH AN ELLIPTICAL CEILING COVERING THE CENTER DOOR. IT HAS A DENTILLATED CORNICE AND AN ELLIPTICAL ARCH WITH A KEystone BETWEEN TWO PAIRS OF ROMAN DORIC COLUMNS. THERE IS A 3-PART FLAT HEADED WINDOW ON THE SECOND FLOOR OVER THIS PORCH. THERE ARE 7 DORMERS



THE EAST FACADE IS 5 BAYS DEEP ON THE FIRST AND SECOND FLOORS, AND THREE BAYS ON THE THIRD (ATTIC) FLOOR. THERE IS A SEMI-CIRCULAR WINDOW



SEE INSTRUCTIONS

pos direction  
to north  
(see plan)

interesting?  
did you just  
visit?  
YES

do think  
should  
be more  
direct?  
not?

lined on the  
abacus?

Architecturally a well-  
executed building.

## 8. SIGNIFICANCE

F-6-21B

## PERIOD (Check One or More as Appropriate)

- ☐ Pre-Columbian      ☐ 16th Century      ☐ 18th Century      ☒ 20th Century  
☐ 15th Century      ☐ 17th Century      ☐ 19th Century

## SPECIFIC DATE(S) (If Applicable and Known)

1905

## AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- |  |                                      |  |   |
|--|--------------------------------------|--|---|
| <input type="checkbox"/> Aboriginal              | <input type="checkbox"/> Education   | <input type="checkbox"/> Political           | <input type="checkbox"/> Urban Planning             |
| <input type="checkbox"/> Prehistoric             | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Philosophy | <input checked="" type="checkbox"/> Other (Specify) |
| <input type="checkbox"/> Historic                | <input type="checkbox"/> Industry    | <input type="checkbox"/> Science             | _____ MEDICINE _____                                |
| <input type="checkbox"/> Agriculture             | <input type="checkbox"/> Invention   | <input type="checkbox"/> Sculpture           | _____   |
| <input checked="" type="checkbox"/> Architecture | <input type="checkbox"/> Landscape   | <input type="checkbox"/> Social/Humanitarian | _____   |
| <input type="checkbox"/> Art                     | <input type="checkbox"/> Literature  | <input type="checkbox"/> Theater             | _____   |
| <input type="checkbox"/> Commerce                | <input type="checkbox"/> Military    | <input type="checkbox"/> Transportation      | _____   |
| <input type="checkbox"/> Communications          | <input type="checkbox"/> Music       |  |   |
| <input type="checkbox"/> Conservation            |                                      |  |   |

## STATEMENT OF SIGNIFICANCE

ORIGINALLY A TUBERCULOSIS SANATORIUM THE VICTOR CULLEN INSTITUTE HAS HAD VARIOUS OTHER USES, INCLUDING: AS A HOME FOR JUVENILE DELINQUENTS, AND PRESENTLY AS A HOME FOR RETARDED PERSONS.

ARCHITECTURALLY THE MAIN BUILDING IS A VERY FINE EXAMPLE OF THE SKILLFUL COMBINATION OF THE COLONIAL REVIVAL WITH EARLY 20th CENTURY CONTEMPORARY ARCHITECTURE. THE DETAILING IS ESPECIALLY GOOD.

→ similar to the so called Prairie style

ARCHITECT —

THERE IS A DISTINCT RESEMBLANCE BETWEEN THIS BUILDING AND A HOUSE CLOSEBY. THAT IS, TIPAHATA (F-18-59) WHICH WAS BUILT CONTEMPORANEOUSLY, 1904-06.

VICTOR CULLEN INSTITUTE COMMANDS A DISTINCT VIEW INTO THE HARBAUGH VALLEY AND IS VISABLE FROM MANY POINTS. TO LOSE THIS MAIN BUILDING WOULD LEAVE THE INSTITUTE WITHOUT A VISUAL FOCAL POINT, LEAVE IT WITHOUT A CENTER.

style  
unmanned  
check  
William

SEE INSTRUCTIONS

United States Department of the Interior  
National Park Service

**National Register of Historic Places**  
**Continuation Sheet**


Cullen, Victor, Center  
Old Administration Building  
Frederick County, Maryland

*F-6-21B*

~~F-1-6-21B~~

Section number 10 Page 10.1

boundary map, 1990






Cullen, Victor,  
Center Old  
Administration  
Building


F-6-21B

Frederick Co. 42°30'  
Maryland

18/289350/4398380

5463 11 NE  
(SMITHSBURG)






BLUE RIDGE  
SUMMIT QUAD  
(FREDERICK CO.)



F-6-21B



Cullen, Victor, Center Old Administration Building  
Frederick County, Maryland

23 November 1988

Photo: Ronald L. Andrews

Neg.: MD State HPO

Southwest elevations

1/13

Cullen, Victor, Center Old Administration Building  
Frederick County, Maryland

23 November 1988



Photo: Ronald L. Andrews

Neg.: MD SHPO

South elevation detail

2/13

F-6-21B





Cullen, Victor, Center Old Administration Building  
Frederick County, MD

23 November 1988

Photo: Ronald L. Andrews

Neg.: MD SHPO

South elevation door detail

3/  
13

Cullen, Victor, Center Old Administration Building  
Frederick County, MD

23 November 1988

Photo: Ronald L. Andrews

Neg.: MD SHPO

West elevation door detail

4/  
13

F-6-21B



Cullen, Victor, Center Old Administration Building  
Frederick County, MD.

23 November 1988

Photo: Ronald L. Andrews

Req: MD SHPO

West elevation detail

5/13

Cullen, Victor, Center Old Administration Building  
Frederick County, MD.

23 November 1988

Photo: Ronald L. Andrews



Req: MD SHPO

West elevation door detail

6/13



F-6-21B





Callen, Victor, Center Old Administration Building  
Frederick County, MD  
23 November 1988  
Photo: Ronald L. Andrews  
Neg: MD SMP2  
Northwest elevations

7/13

Callen, Victor, Center Old Administration Building  
Frederick County, MD  
23 November 1988  
Photo: Ronald L. Andrews  
Neg: MD SMP2  
Southeast elevations

8/13

F-6-21B



Cullen, Victor, Center Old Administration Building  
Frederick County, MD  
23 November 1988  
Photo: Ronald L. Andrews  
Neg: MD SHPO  
Elevation detail



9/  
13

Cullen, Victor, Center Old Administration Building  
Frederick County, MD  
23 November 1988  
Photo: Ronald L. Andrews  
Neg: MD SHPO  
Interior, Main staircase detail

10/  
13



F-6-21B



Cullen, Victor, Center Old Administration Building  
Frederick County, MD

23 November 1988

Photo: Ronald L. Andrews

Obj.: A.D. SHPO

interior, main staircase detail

11/  
13

Cullen, Victor, Center Old Administration Building  
Frederick County, MD

23 November 1988

Photo: Ronald L. Andrews

Obj.: A.D. SHPO

interior, 2nd floor front hall

12/  
13



F-6-21B



Cullen, Victor, Center Old Administration Building  
Frederick County, MD  
25 November 1988  
Photo: Ronald L. Andrews  
Neg: MD SHPO  
Interior, 2nd Floor room

13/  
13

F-6-021B

Victor Cullen School Old Administration Building

Cullen Drive, Sabillasville

Jennifer K. Cosham, 25 April 2006



South and west facades



Detail, south facade





F-6-21B  
DJA  
Mar, 1978

Md. TB Sanatorium

Administration Bldg  
2<sup>nd</sup> floor infirmary  
over dining room



F6-230

Md. TB Sanatorium

Rear of Administration Bldg

DJA  
Mar., 1978





5-6-21B

Nld. TB Sanatorium  
Adm. Bldg & Dining Room

MJA  
3/78



F-6-21B

Nd. TB Sanatorium

Chapel

JTA  
Mar., 1978



F-6-21B

Nd TB Sanatorium

Reception Hospital Kitchen  
and Dining Room

MJA  
March, 1978





F-6-21B

Old TB Sanatorium

Laboratory Bldg

NTA

Mar., 1978



Md. TB Sanatorium  
Victor Cullen

Administration Bldg.  
~~F-10-57~~ F-6-21B

~~Handwritten scribble~~

P. 1

64/12/10





NR

F-6-21B

Victor Cullen Center/School  
Old Administration Bldg  
Frederick Co

23 Nov 1988

R. Andrews